

Neptune Road Improvements

from Partin Settlement Road to US 192


Project Development and Environment Study



MetroPlan Orlando Winter 2020

Project Location and Limits






Purpose and Need

Capacity

- 2018 daily traffic = 25,000 vehicles
- 2018 volume to capacity = 1.4
- 2045 daily traffic = 32,000 vehicles
- 2045 volume to capacity = 1.8

Safety

- 195 crashes in 5-years
- 3 fatalities, 187 injuries
- Crashes per year nearly doubled
 - 28 in 2013
 - 55 in 2017



Partin Settlement Road to Ames Haven Road

Alternative 1 (North)
Widening occurs
primarily to the north.



Alternative 2 (South)

Widening occurs primarily to the south and requires relocation of power poles to the north side of Neptune Road.




Ames Haven Road to Old Canoe Creek Road

Alternative 1 (North) & Alternative 2 (South)

From Ames Haven Road to the canal just east of the Turnpike, widening occurs on both sides of the road.

From east of the canal to Old Canoe Creek Road, widening occurs to the south.





Old Canoe Creek Road to US 192

Alternative A (4-lane)
Improvement is
constructed within the
existing right-of-way.

Alternative B (5-lane)
Improvement includes
center two-way left-turn
lane and requires
additional right-of-way
from the north side of
Neptune Road.





April 11, 2019 Meeting

- 69 People signed in
- 29 Comments
- 13 Prefer Alternative 1 (North)
- 5 Prefer Alternative 2 (South)
- 0 Prefer Alternative A (4-Lane)
- 3 Prefer Alternative B (5-Lane)
- 4 Want to reduce impacts
- 1 Wants median east of Old Canoe Creek Road









Recommended Preferred Alternative

Partin Settlement Road to Old Canoe Creek Road

- Alternative 1 (North)
 - With adjustments to reduce impacts

Reasons

- Less relocations
- Lower construction cost
- Estimated lower right-of-way cost
- Similar environmental impacts to Alternative 2 (South)

Old Canoe Creek Road to US 192

- Alternative B (5-Lane)
 - With adjustments to reduce right-of-way costs


Reasons

Better operation

Total Program Cost \$ 63,000,000 ±



Next Steps - Schedule



Next Steps

- Public Hearing
- Respond to comments.
- Finalize document and list commitments
- County Commission selects
 Preferred Alternative
- Design
- Right-of-Way acquisition
- Construction

Notes: Schedule is subject to change

TBD = To be determined



Contact Information


Joshua DeVries, AICP

Director of Planning/Senior Planner
Department of Transportation and Transit
Osceola County Government
1 Courthouse Square, Suite 3100
Kissimmee, FL 34741
Joshua.DeVries@Osceola.org

Clif Tate, PE

Project Manager
Engineer of Record
Kimley-Horn and Associates, Inc.
189 S. Orange Ave., Suite 1000
Orlando, FL 32801
Clif.Tate@Kimley-Horn.com





Neptune Road Improvements

from Partin Settlement Road to US 192

Project Development and Environment Study



MetroPlan Orlando Winter 2020